

Frogmore Junior School

Education, Reinforced Bituminous Membrane



Client: Hampshire County Council
Contractor: Salnor Roofing Services Ltd
Completed: January 2018

Size: 1300m²
System Used: Reinforced Bituminous Membrane System

Frogmore Junior School

Langley was selected to complete a full condition survey of the flat roofs on Frogmore Junior School as part of an upgrade to the buildings. All roofs were found to be dry, thus enabling an overlay of the existing roof system to give an extended lease of life, negating the need for a complete replacement.

Internal rainwater outlets were refurbished and new rooflights installed. Extensive preparation work included removing redundant penetrations and raising the window cill level. A bespoke perimeter detail was also installed to allow for a new insulated perimeter cladding system.

Langley Approved Contractor Salnor Roofing Services Ltd carried out the work to an excellent standard, during term time, and the school has peace of mind thanks to a 20-year insurance-backed guarantee which includes, in this case, the existing roof build-ups examined in the detailed Langley survey.

Main System Products:

- Paradiene S VV
- Parafoam Ultra
- Adepar JS
- Paradiene [35] S R4
- Elastoflex GS
- Parathane Mastic
- Parathane Reinforcement Mat
- Parathane Solvent
- Rooflight Scheme
- Supra coating



CASE STUDY

Langley Waterproofing Systems Ltd

Langley House, Lamport Drive, Heartlands Business Park, Daventry, Northants. NN11 8YH
Tel: 01327 704778 Fax: 01327 704845 Email: enquiries@langley.co.uk Website: www.langley.co.uk